Call or (800) 242-8511 www.DiggersHotline.com

ggersHottline C

THOMAS NORDLOH ASSOCIATES
Landscape Architecture
&
Project Management
4111 Taft Rd, Kenosha Wi 53142

COPYRIGHT NOTICE

THIS LANDSCAPE PLAN HAS BEER CREATED BY THOMAS NORBLOH, REGISTERED LANDSCAPE ARCHITECT, AND IS PROTECTED BY US. COPY RIGHTS LAWS. UNAUTHORIZED USE OF DIGITAL AND OR IN PRINTED FORM, COPING, LENDING IN PART AND OR WHOLE IS STRICTLY PROHIBETED UNLESS WRITTEN PERMISSION HAS BEEN GRANTED BY THOMAS NORDLOH, THOMAS NORDLOH ASSOCIATES AND/OR NORDLOH INDUSTRIES, LLC

Landscape Architecture

Project Management

QUICK STORAGE ALADONIA, WISCONSIN

Thomas H. Nordloh Landscape Architect Reg. # 057-000629

Project 20250826

Date 8-29-25_1
Scale

Sheet L-1.0

Call or (800) 242-8511 www.DiggersHotline.com

COUNTY OF RACINE, WISCONSIN

Project 20250826 8-29-25 1


L-2.0

REFERENCE NOTES SCHEDULE


SYMBOL	CODE	DESCRIPTION	QTY
Planting			
, , , , , , , , , , , , , , , , , , ,	32-93-2	SHORT TERM DOUBLE NET STRAW EROSION CONTROL BLANKET OVER MULCH BEFORE INSTALLING PLANTS, INSTALL WITH METAL STAKES FULLY INSTALLED IN SOIL. DO NOT USE LONG TERM EROSION BLANKET.	25,086 st
Planting Ad	cessories		
775/	32-94-119	SHREDDED BARK MULCH, 3-4" DEPTH	3,975 sf
	32-94- 36	3' DIAMETER MULCH TREE RING	9
	32-95-01	EDGE, SHOVEL OUT BED EDGE, 4" DEPTH-SEE DETAIL	<i>0</i> 6 f


PLANT SCHEDULE

SYMBOL	CODE	BOTANICAL / COMMON NAME	SIZE	CONTAINER	QTY
TREES					
	ACE FRE	Acer freemanii 'Jeffersred' TM / Jeffersred Autumn Þlaze Maple	2.5" Cal.	B&B	3
	CEL 0C2	Celtis occidentalis / Common Hackberry	2.5" Cal.	B&B	3
	GYM KEN	Gymnocladus dioica / Kentucky Coffee Tree	2.5" Cal.	B&B	3
	ULM M <i>O</i> R	Ulmus x 'Morton Accolade' TM / Accolade Elm	2.5" Cal.	B&B	3
SHRUBS					
	COR BA2	Cornus sericea 'Þailey's Redtwig' / Red Twig Dogwood	ゔ Ht.		18
	HYD LIM	Hydrangea paniculata `Limelight` TM / Limelight Hydrangea	ゔ Ht.		4
	ROS FRA	Rosa rugosa 'Frau Pagmar Hastrup' / Frau Pagmar Hastrup Rose	5 gal.		10
	VIB EXE	Viburnum dentatum 'Arrowwood' / Arrowwood Viburnum	ゔ Ht.		8
SHRUB EV	ERGREENS	3			
	JUN <i>O</i> LD		5 gal.		2
	JUN FØR	Juniperus chinensis 'Sea Green' / Sea Green Juniper	5 gal		8














GENERAL LANDSCAPE NOTES;

- 1. Topsoil return to depth of 6" minimum is by excavating contractor. Returned topsoil to have no rock larger than 1", construction debris and/or roots in the soil. Contact general contractor if soil is not acceptable for proper plant growth.
- 2. Always contact Diggers Hotline (800-242-8511) or JULIE 811 (or 1-800-892-0123) before proceeding with any work.
- 3. Landscape contractor is required to visit the site and review all civil plans related to the project. The civil plans take precedence over the landscape plans.
- 4. Plant material to be of the highest quality available and should not include # 2 grade trees, evergreens or shrubs. Landscape contractor is to verify plant quantities Labeled plants have precedence over the plant table. Verify quantity with a hand takeoff of the plan. Any substitutions of plant type, quantity or size must be approved by city forester.
- 5. Planting beds shall receive a 3" layer of high quality non-dyed shredded hardwood mulch. 3' diameter tree rings shall be installed around all trees and evergreens in the turf areas.
- 6. Spade cut plant beds and tree rings with a 4" deep shovel cut.
- 7. Seeded lawn areas to have high quality Bluegrass seed blend for sunny areas, shade areas to have a Bluegrass and Fescue blend of seed. See civil plans for turf restoration. Apply a 10-10-10 starter fertilizer after turf has germinated. Follow manufactures direction on fertilizer application rates.
- 8. Erosion blanket shall be installed using 90 day single net, double net or Turf Reinforcement Mats shall be installed per the required use. Follow manufactures stapling guidelines to ensure proper stabilization. Install erosion blanket for dormant seed applications (after November 1st) or mid-summer installations or where ever applicable to promote healthy turf establishment.
- 9. Landscape contractor is responsible to maintain the site for a period of 45 days after substantial completion of project. This will include watering, mowing of turf areas as needed, weeding plant beds, maintaining a clean site and other activities to ensure proper growth of the landscape.
- 10. If an irrigation system is not installed a temporary irrigation system shall be set up for a period of 30 days to water lawn areas. Install drip irrigation for plant beds. Install timers that will enable the new turf areas to receive enough water to properly germinate seed. Owner to provide access to water from outside of building to facilitate proper watering. Seed areas may require additional time for proper establishment
- 11. Warranty of plants, trees, evergreens, shrubs shall be for a period of 18 months from date of substantial completion. One replacement will be required of each dead plant at the end of the warranty period.